

Building requirement:

Building is to be insulated according to Fremont County standards which are blanket insulation with an R-10 factor around slab; R-13 factor on all exterior walls; and an R-30 factor on ceiling.

Interior walls shall be 2x4 construction with 5/8 inch dry wall throughout, 16" on center.

Ceiling Joist w/storage-unbraced. Spaced12', #2 Fir, 16" on center, 2x6.

Overhead propane heaters (two) will heat the building.

Interior doors 36" (5). Bi-fold doors at utility area, exterior doors (3) 36".

Plumbing. To septic system tank all drains from bathroom, utility closet and training room. To floor drain storage tank all vehicle floor drains.

Lighting: all uniform in design, switched to designated areas of use. Offices, rest room and training room on their own switch at entry door. Bay area doors with switches to supply area, primary vehicle area, secondary vehicle area, utility area, outside lighting.

Foundation design provided.

Septic design provided.

Plot plan provided.


East side driveway of concrete, rest of parking and access will be gravel.

Please advise Board of any concerns or questions at (719) 371-3893.

Arkansas Valley Ambulance District Coaldale Substation

11998 County Road 45, Coaldale, CO 81222 EMERGENCY SERVICE STATION







LEGEND

SITE BOUNDRY FLOOD PLAIN · · · · · · PROPERTY LINES -

STRUCTURE [

GREY WATER TANK @ SEPTIC TANK MAN HOLE S

ELECTRIC AND PHONE

EXTERIOR LIGHTING (

PROPANE TANK @

500 GAL, FUEL TANK © WITH SECONDARY CONTAINMENT

| Soil Number | Soil % | Description |
|-------------|--------|--|
| 10 | 10.8% | bronell gravelly sandy loam,2 to 15% slopes |
| 74 | 89.2% | mussels-bronell complex, 2 to 15% stopes |



Number of Parking Spots 10 Standard 9'x18

A tract of land located in the Northwest One-Quarter (NW ½) of the Southeast (SE ½) of Section 29, Township 48 North, Range 11 east of the New Mexico Principle Meridian, County of Fremont, State of Colorado, being more particularly

Beginning at the Center one-Quarter @ 1/2) corner of said Section 29; thence S 89° 37' 27" E, a distance of 96.38feet to a point on the Westerly right of way line of Fremont County Road 45; thence S 15° 23' 15" W along said County Road, a distance of 368.71 feet to a point on the Northerly right of way line of Hamilton Creek Road; thence S 72° 51′ 57″ W along said Hamilton Road, a distance of 416.48 feet to a pint on the North-South centerline of said section; thence N 00° 12′47″ E, a distance of 416 feet to the point of begining

Existing

0.SF

Overall 57,819 SF 100% Building 2400 SF 4.1%

> Proposed 2400 SF

Facility Setbacks: North 25.0' Heights: Steel Building 20

West 30.0' East 50.01

Address: 11998 County Road 45 Howard, Colorado 81240

Existing Zone: Agricultural Living Existing use; Agricultural living

Uses:

4.3.4.10 Emergency Services Station

Site Notes:

- 1. No internal roadways are proposed
- 2. No pedestrian walkways are planned.
- No landscaping is proposed.
- Off-street parking area lighting is provided by a light on the northwest & Southeast sides of the structure. No additional lighting is proposed.
- 5. No known easements are located on the subject property
- No proposed easements are anticipated.
 The site is located in a FEMA flood area.

- Significant natural features are not on the property.
 Drainage structures are not located on the property and are not anticipated.
- 10. No Refuse, Daily carry out.
 11. No phone line. Relying on cell service

| Use | Required Spaces | Proposed Spaces | Explanation | | | |
|---|--------------------|--------------------|---|--|--|--|
| Emergency Service Station (2400 sq. ft.) | 10 | 10 | includes ambulance employee spaces | | | |

PARKING TABLE

Proposed Structures table

SHOP/OFFICE 40'X60' 2,400 SF BUILDING HEIGHT 20'

| DRAWN BY: J.M. SCHLUP DATE: 2/19/2022 | APPOVED BY: PROV. NO. | |
|---|---------------------------------------|--------|
| SURVEYE NO.467 | DWG | |
| REVISIONS, 2/1/2022 | | |
| | I PETITE CHARLES | |
| PROJECT: ARKANSAS VALLEY AMBULANCE DISTRICT 11998 COUNTY ROAD 45 FREMONT COUNTY | SHT, NAME COMMERCIAL DEVELOPMENT PLAN | 1 OF 1 |

NOTES AND SPECIFICATIONS:

FIELD SIZE AND CALCULATIONS:

SITE AND SOIL EVALUATION BY LONG TERM ACCEPTANCE RATE NUMBER OF KITHCHENS: NUMBER OF BATHROOMS: BASED ON NUMBER OF EMPLOYEES: 0.5 GAL / SQ, FT, / DAY 150 GAL/DAY COMPLETED DECEMBER 9, 2021 JESIK CONSULTING 1 KITCHENETTE 1 (1 SHOWER, 1 TOILET, 2 SINKS)

TRENCH WITH INFILTRATORS

18 DUICK 4's

REQUIRED # OF QUICK 4's: ENGINEERED FIELD TYPE:

GENERAL SYSTEM NOTES:

SYSTEM MUST BE INSTALLED WITH THE INDICATED NUMBER OF SYSTEM MUST BE INSTALLED BY QUALIFIED AND LICENSED INSTALLER ANY PORTION OF THE ABSORPTION FIELD MUST BE AT LEAST 150 ft FROM REFER TO LOCAL CODES AND REQUIREMENTS BEFORE INSTALLATION

INSTALLED AT DIFFERENT ELEVATIONS SEE FIELD CROSS SECTION FOR ALL LATERALS MUST BE INSTALLED LEVEL. INDIVIDUAL ZONES MAY BE APPROVAL IS OBTAINED BY THE DESIGN ENGINEER ADDITIONAL INFORMATION.

INFILTRATORS, ZONES, AND PIPE LENGTH UNLESS SPECIFIC WRITTEN

FAMILIAR WITH THE STANDARDS FOR SYSTEM INSTALLATIONS FOR THESE (ELBOWS, VENTS, VALVES, ETC.) AND IT IS ASSUMED THE INSTALLER IS WITHIN FIVE FEET OF THE SEWER EXIT FROM THE FOUNDATION. NON-SPECIFIED COMPONENTS. NOT ALL COMPONENTS ARE SPECIFICALLY SHOWN ON THESE PLANS A SEWER CLEAN-OUT MUST BE INSTALLED OUTSIDE THE STRUCTURE AND

(LIVESTOCK AREAS, VEHICLE TRAFFIC, CONSTRUCTION AREAS, STORAGE COMPACT THE SOILS, FLOOD THE FIELD, DAMAGE THE PIPES, OR THE ABSORPTION FIELD MAY NOT BE USED FOR ANY ACTIVITIES THAT MAY NEGATIVELY INSPACT THE OPERATION OF THE FIELD IN ANY MANNER

TANK NOTES AND SPECIFICATIONS:

CERTIFICATION


AND ENVIRONMENT (COPHE) TANKS SHOULD BE APPROYED BY THE COLORADO DEPARTMENT OF HEALTH

GENERAL TANK NOTES & SPECIFICATIONS:

GROUND SURFACE TANKS MUST BE NO DEEPER THAN 4 FT FROM THE TOP OF TANK TO THE

FT OF SOIL DEEPER THAN 2 FT THAN 2 FT DEEP, THE TANK SHALL SUPPORT AN ADDITIONAL 100 PSF PER EA 400 PSF UNIFORM LOAD PLUS 2,500 POUND AXLE LOAD. WHEN BURIED MORE TOP OF TANKS MUST BE DESIGNED AND CONSTRUCTED TO SUPPORT A MIN

INSTRUCTIONS. TANKS MUST BE INSTALLED PER LOCAL CODE AND THE MANUFACTURERS







ARK VALLEY AMBULANCE

OWTS PLAN FOR: 11998 COUNTY ROAD 45 FREMONT COUNTY, COLORADO



800 W. B) H. STREE F PUEBLO, COLORADO 81003 (719) 582-5388 ww.jcsik.us





DURING BACKFILL (SEE REPORT FOR CAUTION ON HYDROSTATIC LOADS)

-DO NOT ALLOW LARGE MACHINE TRAFFIC DURING BACKFILL

BACKFILL AROUND THE FOUNDATION SHOULD BE MOISTURE CONDITIONED AND WELL COMPACTED. THE FINAL GRADE SHOULD BE SLOPED TO PREVENT PONDING OF WATER ADJACENT TO FOUNDATION WALLS.

BACKFILL SHOULD NOT CONTAIN ROCKS OVER 6" IN DIAMETER OR ANY CONSTRUCTION DEBRIS.


DO NOT DIKE OR IMPEDE THE FLOW OF WATER AWAY FROM FOUNDATON WALLS. DOWNSPOUTS AND SILL COCKS SHOULD DISCHARGE A MIN. OF 5' FROM THE FOUNDATION.




800 W. 8th Street Pueblo, CO (719) 582-5588 www.jesik.us SURFACE WATER DRAINAGE

SCALE:


1:16



FOUNDATION: PLAN REFE TO MAKEN THE POLICE OF THE STALL MAKEN THE POLICE OF THE STALL MAKEN ALL DEFINION A. B. C. C. MIC OF THE FOOT HAVE THE STALL MICHIGAN FACT.







GENERAL NOTES

Fabrication shall be in accordance with A.S.C. standard practices in compliance with the applicable sections, relating to design requirement and allowable stresses of the latest edition of the "AWS Structural Welding Code D1.1 and D1.3".

| .2 | MATERIALS | ASTM DESIGNATION | MIN. YIELD STRENGTH |
|----|-------------------------------------|------------------|---------------------|
| | Hot Rolled Steel Shopes (W, & C) | A572 | Fy = 50 KSI |
| | Hot Rolled Steel Angles (L) | A36 | Fy = 36 KSI |
| | Steel Pipes | A500 | Fy = 42 KSI |
| | Structural Tubing | A500 | Fy = 42 KSI |
| | Structural Steel Web Plate | A572/A1011 | Fy = 50 KSI |
| | Structural Steel Flange Plates/Bars | A529/A572 | Fy = 55 KSI |
| | Cold Formed Light Gage | A653/A1011 | Fy = 55 KSI |
| | Roof and Wall Sheets | A792/A653 | Fy = 50, 80 KSI |
| | Cable Brace | A475 - TYPE 1 | Extra High Strength |
| | Rod Brace | A36 | Fy = 36 KSI |

MIN. TENSILE STRENGTH Machine Bolta & Nute High Strength Bolta (1"# and less) High Strength Bolta (>1"# to 1 1/2"#) Anchor Bolts (Not supplied by A.S.C.) Fu = 60 KSI Fu = 120 KSI Fu = 105 KSI A307 A325-TYPE 1

Fu = 60 KSI

PRIMER
Shop primer point is a rust inhibitive primer which meets the end
performance of Federal Specification SSPC No. 15 and is A.S.C. Gray Oxide
color. This point is not intended for long term exposure to the elements.
A.S.C. is not responsible for any deterioration of the shop primer point
as a result of improper handling and/or jobsite storage.
A.S.C. shall not be responsible for any field applied paint and/or coatings.
(AISC Code of Standard Practice, Latest Edition).
Nominal thickness of primer will be 1 mil unless otherwise
specified in contract documents.

GALVANIZED OR SPECIAL COATINGS:

ALL BOLTS ARE 1/2"6 x 0"-1 1/4" A307 EXCEPT :

a) Endwall rafter splice - 5/8"\$\sim x 0'-1 3/4" A325-N
b) Endwall column to rafter connection - 1/2"\$\sim x 0'-1 1/4" A325 MIN.(SEE WALL ELEVATION)
c) Main frame connections - SEE CROSS SECTION
d) Flange Brace connections - 1/2"\$\sim x 0'-1 1/4" A325

NOTE: Workers are not supplied unless noted otherwise on drawing

A325 BOLT TIGHTENING REQUIREMENTS

All high strength botts are A325—N unless specifically noted otherwise. Holes are not slotted and design is bearing connection.

Structural botts shall be tightened by the turn-of-the-nut method in accordance with the Latest Edition AISC "Specification For Structural Joints" using ASTM A325 or A490 Botts, when specifically required. A325—N botts are supplied without washer unless otherwise noted on the drawings.

All boilted connections unless noted are designed as bearing type connections with boilt threads not excluded from the shear plane.

CLOSURE STRIPS ARE FURNISHED (IF ORDERED) FOR APPLICATION:

INSIDE- Under roof panels & base of wall panels
OUTSIDE - Between roof panels & ridge cap
- Between wall panels & eave/gable trim

ERECTION NOTE:

All bracing, strapping, & bridging shown and provided by A.S.C. for this building is required and shall be installed by the erector as a permanent part of the structure. If additional bracing is required for stability during erection, it shall be the erector's responsibility to determine the amount of such bracing and to procure and install as needed.

ERECTION AND UNLOADING NOT BY A.S.C.

Any cloims or shortages by buyer must be made to A.S.C. within five (5) working days after delivery, or such claims will be considered to have been walved by the customer and disallowed.

CORRECTIONS OF ERRORS AND REPAIRS (MBMA 6.10)
Claims for correction of olleged misfits will be discliowed unless A.S.C. shall have received prior notice thereof and allowed reasonable inspection of such misfits. The correction of minor misfits by the use of drift plas to drow the components into line, moderate amounts of reaming, chipping and cutting, and the replacement of minor shortages of material are a normal part of erection and are not subject to claim. No part of the Building may be returned for alleged misfits without the prior approval of A.S.C.

BUYER/END USE CUSTOMER RESPONSIBILITIES

It is the responsibility of the BUYER/END USE CUSTOMER to obtain appropriate opprovals and secure necessary permits from City, County, State, or Federal Agencies as required, and to advise/release A.S.C. to fabricate upon receiving such.

Armstrong Steat Corp (heraciter referred to as A.S.C.) standard specifications apply unless atliquiated otherwise in the Contract Documents. A.S.C. design, fabrication, quality criteria, standards, practice, methods and tolerances shall govern the work with any other interpretations to the contrary notwithstanding. It is understood by both Porties that the BUYER/END USE CUSTOMER is responsible for clarification of inclusions or exclusions from the architectural plans and/or specifications, in case of discrepancies between A.S.C. structural steel plans and plans for other trades, A.S.C. plans shall govern. (Section, 3 AISC Code of Standard Practices, Latest Edition) Armstrong Steel Corp (hereafter referred to an A.S.C.)

Approval of A.S.C. drawings and calculations indicates that A.S.C. has correctly interpreted and applied the Contract Documents. This approval constitutes the contractor/owners acceptance of the A.S.C. design concepts, assumptions, and loading. (Section 4 AISC Code and MBMA 3.3.3)

Once the BUYER/ENO USE CUSTOMER has signed A.S.C. Approval Package and the project is released for fabrication, changes shall be billed to the BUYER/ENO USE CUSTOMER including material, engineering and other costs. An additional fee may be charged if the project must be moved from the fabrication and



PHONE: 800-345-4610 www.armstronasteel.com

JOB NO.: 55101

CUSTOMER: CHRIS BERTOLINO AND/OR POST SCRIPTS LLC

END USER : CHRIS BERTOLINO

END USE : WORKSHOP

LOCATION : 18 ALTA VISTA RD

: COTOPAXI, CO 81223

: FREMONT COUNTY

PH. NO. : 409-392-5658 EMAIL: POSTSCRIPTSLLC@GMAIL.COM

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH THE FOLLOWING AS INDICATED:

| DESIGN LOADS: | | BUILDING DESCR | RIPTION: | |
|---------------------------------------|-------------------------|---------------------------|---|------|
| Design Code / Wind Code | : IBC-15 | Width (ft) | : 40 | In |
| Building Risk Category | :II — Normal | Length (ft) | : 60 | |
| Enclosure | : Closed | Eave Ht. at BS\ | | |
| Dead Load (psf) | : 2.00 | Eave Ht. at FSV | | |
| Collateral Load (psf) | : 2.00 | Roof Slope at E | | |
| Wind Load | | Roof Slope at I | | |
| Ultimate Wind Speed, (Vult) (mph) | :145.00 | Bay Spacing (fi |) :3 at 20 | |
| Wind Exposure | : C | COVERING AND | TRIMS: | |
| Internal Pressure Coefficient, GCpi | :0.18 /-0.18 | Roof Panels & | | |
| Wall Panel Design Wind Pressure (psf) | : 46.7/-50.7 | Panel Type | :26 Ga. R-Loc | |
| Live Load | | Panel Color | : Galvalume Plus | |
| Primary Framing (psf) | 20.00 | Trim Colors | . Galvalattle 1 las | |
| Trib. Area Reduction | : No | | Trim Lt. Stone 40 yr | |
| Secondary Framing (psf) | : 20.00 | Gaple, East | FIGURE STORE TO JE | |
| Snow Load | | Wall Panel & Ta | ina a | |
| Ground Snow Load, Pg (psf) | : 45.00 | | : 26 Ga. R-Loc | |
| Roof Snow Load, Pf (psf) | : 45.00 | Panel Type Panel Calor | : Desert 40 yr | |
| Sloped Roof Snow Load, Ps (psf) | : 45.00 | Trim Colors | Desert 40 yr | |
| Snow Exposure Factor, Ce | :1.00 | Corner Trir | - Ilt Stone 40 im | |
| Snow Importance Factor, Is | :1.00 | | (8) | |
| Thermal Factor, Ct | :1.20 | Opening Tr Base Trim | Desert 40 yr | |
| Sloped Factor, Cs | : 1.00 | buse min | Desert 40 yr | |
| Seismic Load | | | | |
| Seismic Importance Factor, le | :1.00 | | | |
| Site Class | :D | | | |
| Mapped Spectral Response Acceleration | | 0.081 | | |
| Spectral Response Coefficients | : Sds = 0.272 : Sd1 = | 0.130 | | |
| Seismic Design Category | :B | | | |
| Basic Force Resisting Systems Used | :Steel System Not Spe | | | |
| | Detailed For Resistanc | е | | |
| | :Rigid Frames (OMF) | | | |
| | :Braced Frames (OCBF, | /OMF) | | |
| Total Design Base Shear, V (kips) | :Longitudinal = 3.62 | | | |
| | :Transverse = 3.32 | | | |
| | | | | |
| Response Modification Factors, R | :Rigid Frames = 3.50 | $\Omega = 3.00$ | | |
| | :SW X-Bracing = 3.25 | $\Omega = 2.00$ | | 0 |
| | :SW Wind Bent = 3.50 | $\Omega = 3.00$ | ÷ | |
| Seismic Response Coefficient, Cs | :Rigid Frames = 0.077 | g | SEALING OF THIS DRAWING DOES N | |
| Solarino reaportae obernolent, oa | :SW X-Bracing = 0.0838 | | IMPLY OR CONSTITUTE THAT ARMS STEEL ENGINEER IS THE ENGINEER | |
| | :SW Wind Bent = 0.00778 | | RECORD OR THE DESIGN PROFESSION | ONAL |
| | | - | FOR THIS PROJECT. ONLY THE DES | PION |

Drawing Name Drawing Cover Anchor Bolt Plan Anchor Bolt Details Anchor Bolt Reactions Rigid Frame Front Sidewall Back Sidewall Left Endwall Right Endwall Roof Plan Details

insulation

Roof Insulation : None Wall Insulation : None

Drawing Index

Page(s)

3

4-7

8

9 10

11 12

13-16

The BUYER/END USE CUSTOMER is responsible for overall project coordination. All Interface, compatibility, and design considerations concerning any materials not furnished by A.S.C. and A.S.C. ateal system are to be considered and coordinated by the BUYER/END USE CUSTOMER. Specific design criteria concerning this interface between materials must be furnished before release for fabrication or A.S.C. assumptions will govern (AISC Code of Standard Practice, Latest Edition).

It is the responsibility of the BUYER/END USE CUSTOMER to insure that A.S.C. plans comply with the applicable requirements of any governing building authorities. The supplying of sealed engineering data and drawings for the metal building system does not imply or constitute an agreement that A.S.C. or its design engineers are acting as the engineer of record or design professional for a construction project. These drawings are sealed only to certify the design of the structural components furnished by A.S.C.

The BUYER/END USE CUSTONER is responsible for setting of anchor boits and ersettion of steel in accordance with A.S.C. "For Construction" drawings only. Temporary supports such as guys, brocas, followork, cribbing or other elements required for the erection operation shall be determined furnished and installed by the erector. No items should be purchased from a preliminary set of drawings, including anchor boits. Use only final "FOR CONSTRUCTION DRAWINGS" for this use. (AISC Code of Standard Practice, Latest Edition.)

Armstrong Steel Corp is responsible for the design of the anchor bott to permit the transfer of forces between the base plate and the anchor bott in shear, bearing and tension, but is not responsible for the transfer of anchor to forces to the concrete or the adequacy of the anchor bott in relation to the

forces to the concrete or the adequacy of the anchor box in resource to whe concrete.

Unless otherwise provided in the Order Documents, A.S.C. does not design and is not responsible for the design, material and construction of the foundation or foundation embedments. The END USE CUSTOMER should assure himself that adequate provisions are made in the foundation design for loads imposed by column reactions of the building, other imposed loads, and bearing capacity of the soil and other conditions of the building sits.

It is recommended that the anchorage and foundation of the building be designed by a Registered Professional Engineer experienced in the design of such structures. (Latest MBMA Low Rise Building Systems Manual)

Normal erection operations include the corrections of minor misfits by moderate amounts of reaming, chipping, welding or cutting, and the drawing of elements into line through the use of drift pins. Errors which cannot be corrected by the foregoing means or which require major changes in member configuration are to be reported immediately to A.S.C. by the BUYER/END USE CUSTOMER, to enable whoever is responsible either to correct the error or to approve the most efficient and economic method of correction to be used by others. (AISC Code of Standard Practice Latest Edition)

Neither the fabricator nor the BUYER/END USE CUSTOMER will cut, drill or otherwise after his work, or the work of other trades, to accommodate other trades, unless such work is clearly specified in the contract documents. Whenever such work is especified, the BUYER/END USE CUSTOMER is responsible for furnishing complete information as to materials, size, location and number of attentions prior to preparation of shop drawings. (AISC Code of Standard Practice Latest Edition)

<u>WARNING</u> In no case should Calvalume steel panels be used in conjunction with lead or copper. Both lead and copper have harmful corrosive effects on the Galvalume allay coating when they are in contact with Calvalume steel panels. Even run-off from copper flashing, wiring, or tubing onto Calvalume should be avoided.

SAFETY COMMITMENT. Armstrong Steel Corp has a commitment to manufacture quality building components that can be safely erected. However, the safety commitment and job site practices of the erector are beyond the control of A.S.C. It is strongly recommended that safe working conditions and occident prevention practices be the top priority of any job site. Local, State, and Federal safety and health standards should always be followed to help insure workers safety. Make certain all employees know the safest and most productive way of erecting a building. Emergency procedures should be known to all employees. Emergency procedures should be known to all employees. Descriptions of the safest and most productive way of erecting a building. Emergency procedures all years and the safest and the safest procedures are also recommended. The use of hard hate, rubber sole shoes for roof work, proper equipment for handling material, and safety nets where applicable, are recommended.

Roof drainage systems (gutter, downspouts, etc.) must be free of any obstruction 2.14 to ensure emooth operation at any given time.

2.15 It is recommended by Factory Mutual (Reference: B2.44) that roofs be cleared of snow when half of the maximum snow depth is reached. The maximum snow depth can be estimated based on the design snow load and the density of snow and/or ice buildup. See Chart below.

| ROOF SNOW LOAD (IN PSF) | EQUIVALENT SNOW HEIGHT AT ROOF (IN INCHES) | RECOMMENDED SNOW HEIGHT WHEN SNOW REMOVAL SHOULD START (IN INCHES) |
|----------------------------|---|--|
| 20 | 16.60 | 8.30 |
| 25 | 17.25 | 8.62 |
| 30 | 17.90 | 8.95 |
| 35 | 18.55 | 9.28 |
| 40 | 19.20 | 9.60 |
| 45 | 19.85 | 9.92 |
| 50 | 20.50 | 10.25 |
| 55 | 21.15 | 10.58 |
| 60 | 21.80 | 10.90 |
| 65 | 22.45 | 11.22 |
| 70 | 23.10 | 11.55 |
| 75 | 23.75 | 11.88 |
| 80 | 24.40 | 12.20 |

For Snow/lee Remaral Procedure, Refer to Metal Building System Manual 2002 Edition, Section A8.4, Page XI-A8-2,

| Ura | WI | па | Statu | 15 |
|-----|----|----|-------|----|
| 100 | | | | _ |

| APPROVAL: REVISED APPROVAL: |
|---|
| These drawings are conceptual only and are not to be used for the permit or construction process. |
| PERMIT/CONSTRUCTION: REVISED PERMIT/CONSTRUCTION: |
| These drawings are Final and are for review by the building official or others. |

ERECTION DRAWINGS:

Drawings to be used for the erection of the building.

JOB NO : 55101 CHRIS BERTOLINO AND/OR POST SCRIPTS LLC


FOR THIS PROJECT. ONLY THE DESIGN OF THE METAL BUILDING SYSTEM AS FURNISHED BY A.S.C. IS INCLUDED.
FOUNDATION ANALYSIS, ELECTRICAL, AND
MECHANICAL SYSTEMS, AND/OR OTHER PARTS SUPPLIED BY ANYONE OTHER


THAN ARMSTRONG ARE SPECIFICALLY EXCLUDED. NO INSPECTION OR SUPERVISION IS IMPLIED.

Equivalent Lateral Force Procedure

Analysis Procedure Used

Other Loads/Requirements







MINOR FIELD WORK OF STRUCTURAL, SECONDARY AND PANEL/TRIM ITEMS MAY BE NECESSARY TO ENSURE PROPER FIT. SUCH WORK IS CONSIDERED A NORMAL PART OF METAL BUILDING ERECTION. A.S.C. WILL NOT HONOR BACKCHARGES FOR MINOR FIELD WORK.

ANCHOR BOLT DIAMETERS HAVE BEEN DESIGNED BY THE METAL. BUILDING MANUFACTURER BASED ON AISC METHOD WITH COMBINED SHEAR AND TENSION.

DEVELOPMENT, EMBEDMENT AND HOOK LENGTH OF ANCHOR BOLTS IN THE CONCRETE ARE DESIGN RESPONSIBILITY OF OTHERS. ALSO DESIGN OF SHEAR ANGLES, TENSION PLATES, HAIRPINS, AND ANY OTHER EMBEDDED MATERAL IN THE CONCRETE SHALL BE DESIGNED AND PROVIDED BY OTHERS.

NOTE: ANCHOR BOLT PROJECTION IS FROM BOTTOM OF BASE PLATE.






THIS DESIGN IS BASED ON RIGID FRAMES @ LINE 1 & LINE 2 ARE TO SUPPORT FUTURE LEAN-TO 10' WDE X 20' LONG X 10' LOW EAVE HT/12'-6" HIGH EAVE HT, 3:12

| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. | |
|-------|---------------------|----------|------|------|------|--|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | ACCHANGING |
| Ε | ERECTION | 06.14.17 | DK | DK | SS | STUSION |
| | | | | | | |
| - | | | | | | 5889 S. Greenwood Plaza Blvd, St Greenwood Village, Colorado 80 |
| | | | | | | PHONE: 800-345-4610 |

| | DESCRIPTION | ANCHOR BOLT DETAILS |
|------|-------------|--|
| | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LLC |
| | END USER | CHRIS BERTOLINO |
| #300 | SCALE | NOT TO SCALE |
| ii | 5510 | 1 DATE: 04/25/17 DWG. NO.: 2 OF 16 SSUE: E |



| IIGID I | FRAME: | | | | 26 | | S, & BAS | E PLATE | ES | | | | |
|-------------|-------------|------------|-------------|-----------------------|-----------------------|-------------|-------------|-------------------------|--------------|---------------|-----------------------|-------|---------------|
| Frm Line | Col Line | Load Id | Hmax H | Jmn_Read V Vmax | tions(k Load Id | Hmin H | V Vmin | Bol [.] Qty | t(in) Dia | Base Width | e_Plate(in) Length | Thick | Grout (in) |
| 1 | D | 1 | 3.6 | 10.4 | 3 | -3.4 | -5.3 | 4 | 0.750 | 6.000 | 12.50 | 0.500 | 0.0 |
| 1 | A | 6 1 | 3.2 -3.5 | -4.3 12.8 | 2 4 | -3.6 2.8 | 7.3 -6.0 | 4 | 0.750 | 6.000 | 12.50 | 0.500 | 0.0 |

| RIGID | GID FRAME: MAXIMUM REACTIONS, ANCHOR BOLTS, & BASE PLATES | | | | | | | | | | | | |
|-------------|---|------------|-------------|-----------------------|-----------------------|--------------|--------------|------------|--------------|--------------|-----------------------|-------|---------------|
| Frm Line | | Load Id | Hmax H | umn_Reac V Vmax | tions(k Load Id | Hmin H | V | Bol Qty | t(in) Dia | Bas Width | e_Plate(in) Length | Thick | Grout (in) |
| 2 | D | 1 | 8.7 | 20.2 | 3 7 | -5.2 -0.5 | -8.0 -8.6 | 4 | 0.750 | 6.000 | 11.50 | 0.500 | 0.0 |
| 2 | A | 6 1 | 4.9 -8.6 | -5.3 22.6 | 1 | -8.6 4.6 | 22.6 -8.7 | 4 | 0.750 | 6.000 | 11.50 | 0.500 | 0.0 |

| RIGID | FRAME: | | MAXIMUM | REACTION | IS, ANCI | HOR BOL | TS, & BASE | PLATI | ES | | | | |
|-------------|--------|------------|-------------|-----------------------|-----------------------|-------------|--------------|------------|--------------|---------------|----------------------|-------|---------------|
| Frm Line | | Load Id | Hmax H | umn_Reac V Vmax | tions(k Load Id | Hrnin H | V Vmin | Bol Qty | t(in) Dia | Base Width | _Plate(in) Length | Thick | Grout (in) |
| 3 | D | 1 | 8.7 | 20.2 | 3 7 | -4.7 0.1 | -7.6 -8.1 | 4 | 0.750 | 6.000 | 11.50 | 0.500 | 0.0 |
| 3 | A | 4 | 4.7 -8.7 | -7.6 20.2 | 1 4 | -8.7 4.7 | 20.2 -7.6 | 4 | 0.750 | 6.000 | 11.50 | 0.500 | 0.0 |

| ı | RIGID F | RAME: | | MAXIMUM | REACTION | IS, ANCI | HOR BOLT | S, & BASE | PLATE | S | | | | |
|---|-------------|-------------|------------|-------------|-----------------------|-----------------------|----------------|--------------|-------------|-------------|---------------|----------------------|-------|---------------|
| | Frm Line | Col Line | Load Id | Hmax H | umn_Reac V Vmax | tions(k Load Id |) Hmin H | V Vmin | Bolf Qty | (in) Dia | Base Width | _Plate(in) Length | Thick | Grout (in) |
| ۱ | 4 | D | 1 | 3.6 | 10.5 | 5 3 | -2.9 -2.8 | -3.2 -4.9 | 4 | 0.750 | 6.000 | 12.50 | 0.500 | 0.0 |
| | 4 | A | 6 1 | 2.9 -3.6 | -3.2 10.5 | 1 | -3.6 2.8 | 10.5 -4.9 | 4 | 0.750 | 6.000 | 12.50 | 0.500 | 0.0 |

| END | NALL | COLUN | IN: | BASIC COLUMN REACTIONS (k) |
|-----------------------|----------------------------|------------------------------------|--|---|
| Frm Line 1 1 | Col Line C B | Dead Vert 0.1 0.1 | Wind Press Horz -3.8 -3.8 -3.8 | Wind Suct Horz 4.2 4.2 4.2 |
| 4 | - | | | 4.2 |
| | Frm Line 1 1 4 | Frm Col Line Line 1 C 1 B | Frm Col Dead Line Line Vert 1 C 0.! 1 B 0.1 4 B 0.1 4 C 0.1 | Frm Col Dead Press Line Line Vert Horz 1 C 0.1 -3.8 1 B 0.1 -3.8 4 B 0.1 -3.8 4 C 0.1 -3.8 |

| ENDWALL | COLUMN: | MAXIMUM REACTIONS, | ANCHOR BOLTS, | & BASE PLATES |
|---------|---------|--------------------|---------------|---------------|
| | | | | |

| | | - | Colu | Jmn_Reac | tions(k |) : | | | | | 6674741420 | | |
|-------------|-------------|--------------|------------|------------|---------|-----------|-----------|------------|--------------|---------------|----------------------|-------|---------------|
| Frm Line | Col Line | Load | Hmax H | V Vmax | Load | Hmin H | V Vmin | Bol Qty | t(in) Dia | Base Width | _Plate(in) Length | Thick | Grout (in) |
| 1 | С | 8 10 | 2.5 2.5 | 0.1 0.1 | 9 | -2.3 | 0.1 | 4 | 0.625 | 6.500 | 6.000 | 0.313 | 0.0 |
| 1 | В | 8 10 | 2.5 2.5 | 0.1 0.1 | 9 | -2.3 | 0.1 | 4 | 0.625 | 6.500 | 6.000 | 0.313 | 0.0 |
| 4 | В | 8 10 | 2.5 2.5 | 0.1 0.1 | 9 | -2.3 | 0.1 | 2 | 0.625 | 3.250 | 6.000 | 0.313 | 0.0 |
| 4 | С | 8 10 | 2.5 2.5 | 0.1 0.1 | 9 | -2.3 | 0.1 | 2 | 0.625 | 3.250 | 6.000 | 0.313 | 0.0 |

| T- | | | | | | | | | | | | | | |
|-------------------------|--------------------------|------------------------------------|--------------------------------|----------------------------------|-----------------------------------|--------------------------------|------------------------------------|--------------------------------|------------------------------------|----------------------------------|----------------------------------|---------------------------------|----------------------------------|--|
| 1 |) FRAI | | | | | IONS (k | | | | | | | | |
| Frame Line 1 | Column Line D A | Do Horiz \ 0.2 -0.2 | ead /ert 0.9 1.0 | ·——Colla Horiz 0.1 —0.1 | teral- Vert 0.4 0.5 | Horiz 1.4 -1.4 | Vert 4.0 5.0 | Horiz 3.2 -3.1 | -Snow Vert 9.1 11.2 | | Left1- Vert -9.8 -5.8 | -Wind_ Horiz 0.6 4.8 | Right1 Vert 5.7 11.1 | |
| Frame Line 1 | Column Line D A | -5.5 | .eft2- /ert -6.5 -2.9 | →Wind_i Horiz 1.0 5.6 | Right2— Vert -2.5 -8.2 | Wind Horiz -0.9 -1.2 | i_Long1- Vert -7.0 -5.5 | Wind Horiz -1.6 -1.9 | l_Long2- Vert -6.2 -6.3 | -Seism Horiz -0.3 -0.4 | ic_Left Vert -0.2 0.2 | Seismic Horiz 0.3 0.4 | Right Vert 0.2 -0.2 | |
| Frame Line 1 | Column Une D A | -Seismic_ Horiz \ 0.0 0.0 | | -MIN_SI Horiz 1.4 -1.4 | NOW Vert 4.1 4.1 | F1UNB_ Horiz 2.5 -2.5 | SL_L- Vert 8.5 4.9 | F1UNB_ Horiz 2.5 -2.5 | SL_R~ Vert 4.9 8.5 | | | | | |
| Frame Line 2 2 | Column Line D A | | | ——Colla Horiz 0.4 —0.4 | Vert | Horiz 3.5 -3.4 | -Live Vert 8.0 8.9 | Horiz 7.8 -7.8 | -Snow Vert 18.0 20.1 | Wind Horiz -9.2 -1.5 | _Left1- Vert -14.8 -9.3 | -Wind_ Horiz 0.1 8.2 | Right1- Vert -9.2 -16.1 | |
| Frame Line 2 2 | Column Line D A | -8.5 | | Horiz | Right2- Vert -3.2 -10.4 | Wind Horiz -1.4 -0.1 | l_Long1 Vert -15.8 -10.7 | Wind Horiz -2.7 -1.4 | I_Long2- Vert -14.2 -12.2 | -Seismi Horiz -0.5 -0.6 | ic_Left Vert -0.4 0.4 | Seismic Horiz 0.5 0.6 | _Right Vert 0.4 -0.4 | |
| Frame Line 2 2 | Column Line D A | -Seismic_ Horiz V 0.0 0.0 | Long /ert -0.9 0.0 | -MIN_SI Horiz 3.5 -3.5 | NO W Vert 8.0 8.0 | F2UNB_ Horiz 6.1 -6.1 | SL_L- Vert 16.7 9.6 | F2UNB_ Horiz 6.1 -6.1 | _SL_R- Vert 9.6 16.7 | | | | | |
| Frame Line 3 3 | Column Line D A | | ead /ert 1.4 1.4 | Colla Horiz 0.4 -0.4 | teral— Vert 0.8 0.8 | Horiz 3.5 -3.5 | Vert | Horiz 7.9 -7.9 | -Snow Vert 18.0 18.0 | Wind Horiz -8.3 -0.1 | Left1- Vert -14.1 -9.2 | -Wind_ Horiz 0.1 8.3 | Right1- Vert -9.2 -14.1 | |
| Frame Line 3 3 | Column Line D A | -8.1 | | -Wind_F Horiz 0.3 8.1 | Right2— Vert -3.6 -8.4 | Horiz | l_Long1- Vert -14.9 -10.4 | Wind Horiz -1.6 0.3 | Long2- Vert -13.3 -12.0 | -Seismi Horiz -0.5 -0.5 | | Seismic Horiz 0.5 0.5 | | |
| Frame Line 3 3 | Column Line D A | | | -MIN_SN Horiz 3.5 -3.5 | NOW Vert 8.0 8.0 | F3UNB_ Horiz 6.1 -6.1 | SL_L- Vert 16.7 9.6 | F3UNB_ Horiz 6.1 -6.1 | SL_R- Vert 9.6 16.7 | | | | | |
| Frame Line 4 4 | Column Line D A | De Horiz V 0.2 -0.2 | | ——Collat Horiz 0.1 —0.1 | teral— Vert 0.4 0.4 | Horiz 1.4 -1.4 | -Live Vert 4.1 4.1 | Horiz 3.2 -3.2 | -Snow Vert 9.2 9.2 | | _Left1- Vert -9.0 -5.7 | −Wind⊥ Horiz 0.6 5.0 | Right1- Vert -5.7 -9.0 | |
| Frame Line 4 4 | Column Line D A | -5.0 · | | -Wind_R Horiz 0.6 5.0 | Right2- Vert -2.9 -6.1 | Wind Horiz 0.2 0.4 | _Long1- Vert -6.1 -5.3 | Wind Horiz -0.4 -0.2 | _Long2- Vert -5.3 -6.1 | -Seismi Horiz -0.3 -0.3 | | Selsmic, Horiz 0.3 0.3 | Right Vert 0.2 -0.2 | |
| Frame Line 4 4 | Column Line D A | -MIN_SNO Horiz V 1.4 -1.4 | | F4UNB_S Horiz 2.5 -2.5 | SL_L- Vert 8.5 4.9 | F4UNB_ Horiz 2.5 -2.5 | .SL_R- Vert 4.9 8.5 | | | | | | | |

| Wc | ıll — | - Col | | React | ions(k) — Sei | ismic - | Panel_She (lb/ft) | ar |
|--------------|--------|-------|--------|-------|-------------------|---------|----------------------|------------|
| Loc | Line | Line | Horz " | Vert | Horz | Vert | | is Note |
| L_EW | 1 | | | | | | | (h) |
| F_SW R_EW | A 4 | 2,3 | | | | | | (<u>a</u> |
| B_SW | Ď | 3.2 | 4.9 | 2.9 | 1.6 | 1.0 | | (n, |

| VIND BENT RE | W | ali — | Col | Wind | l(k) | ctions Seismic | | Bol | t(in) | Base_ | Plate(in) | |
|--------------|--------------|-------|------|------------|------------|-------------------|------|-----|----------------|----------------|------------------|----------------|
| 11 11 | Loc | Line | Line | Horz | Vert | Horz | Vert | Qty | Dia | Width | Length | Thick |
| <u> </u> | F_SW F_SW | A | 2 3 | 3.7 3.7 | 5.1 5.1 | 1.0 | 1.4 | 4 | 0.750 0.750 | 6.000 6.000 | 12.000 12.000 | 0.500 0.500 |
| tv tv | | | | | | | | | | | | |

NOTES FOR REACTIONS

| Building reactions are based on the following building data: | |
|---|-------------|
| Width (ft) | = 40.0 |
| Length (ft) | = 60.0 |
| Eave Height (ft) | = 14.0/14.0 |
| Roof Slope (rise/12) | = 3.0/3.0 |
| Dead Load (psf) | = 2.0 |
| Collateral Load (psf) | = 2.0 |
| Live Load (psf) | = 20.0 |
| Snow Load (psf) | = 45.0 |
| Ultimate Wind Speed (Vult) | = 145.0 |
| Wind Code | = IBC-15 |
| Exposure | - 0 |
| Closed/Open | = č |
| Importance Wind | = 1.00 |
| Importance Seismic | = 1.00 |
| Seismic Zone | = B |
| Selsmic Coeff (Fa*Ss) | = 0.41 |
| (=/ | |

ID Description

TANCHOR BOLT SUMMARY

| Al | NCH | NK BOLI | 50MM/ | AR Y | |
|----|---------------|-----------------------------|----------------------|----------------------|--|
| | Qty | Locate | Dia (in) | Туре | |
| | 12 32 8 | Endwall Frame WindCol | 5/8" 3/4" 3/4" | A307 A307 A307 | |


NOTE:


THIS DESIGN IS BASED ON RIGID FRAMES & LINE 1 & LINE 2 ARE TO SUPPORT FUTURE LEAN-TO 10' WIDE X 20' LONG X 10' LOW EAVE HT/12'-6" HIGH EAVE HT, 3:12


| ISSUE | DESCRIPTION | DATE | DRN. | снк. | DES. | Γ |
|-------|---------------------|----------|------|------|------|----|
| P | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | 1 |
| Ε | ERECTION | 06.14,17 | DK | DK | SS | |
| | | | | | | l |
| | | | | | | 58 |


| | THE PARKS THE COLUMN |
|----|--|
| | SVIEW |
| | |
| 58 | 89 S. Greenwood Plaza Blvd, Ste#300 Greenwood Village, Colorado 80111 |
| | PHONE: 800-345-4610 www.ormstrongsteel.com |
| | |


| - 9 | DESCRIPTION | ANCHOR BOLT REACTIONS | | | | |
|-----|-------------|---|--|--|--|--|
| | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LLC | | | | |
| | END USER | CHRIS BERTOLINO | | | | |
| | SCALE | NOT TO SCALE | | | | |
| | 5510 | 1 OMC. NO.: 3 OF 16 SSUE: E | | | | |


















ENDWALL FRAMING: FRAME LINE 1



NOTE:

MINOR FIELD WORK OF STRUCTURAL, SECONDARY AND PANEL/TRIM ITEMS MAY BE NECESSARY TO ENSURE PROPER FIT. SUCH WORK IS CONSIDERED A NORMAL PART OF METAL BUILDING ERECTION. A.S.C. WILL NOT HONOR BACKCHARGES FOR MINOR FIELD WORK.

ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Ga. R-Loc - Desert 40 yr

| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. | |
|-------|---------------------|----------|------|------|------|--|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | DELYSSECTION |
| Ε | ERECTION | 06.14.17 | DK | DK | SS | STREET |
| | | | | | | |
| | | | | | | 5889 S. Greenwood Plaza Blvd, Step 3 |
| | | | | | | Greenwood Village, Colorado 80111 PHONE: 800-345-4810 |

| | DESCRIP |
|---------------------------------------|---------|
| A A A A A A A A A A A A A A A A A A A | CUSTOME |
| | END USE |
| | |

| | DESCRIPTION | ENDWALL FRAMING & SHEETING |
|-----|-------------|---|
| 300 | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LLC |
| | END USER | CHRIS BERTOLINO |
| | SCALE | NOT TO SCALE |
| 1 | 5510 | 1 PNG. BY: SS PNG. 10 OF 16 SSUE E |

TRIM TABLE
FRAME LINE 1
OID QUAN PART


BA204 Q764102 Q764122 Q765L AR963L

| | TABLE LINE 1 | | |
|------|-----------------|---------|------------|
| NAUC | MARK | PART | LENGTH |
| 2 | EC-1 | 8X35C12 | 15'-1 3/4" |
| 5 | G-1 | 8X25Z16 | 11'-11" |
| 2 | G-2 | 8X25Z14 | 11'-11" |
| 2 | G-3 | 8X25Z16 | 5'-3 1/8" |


| | CONNECTION PLATES FRAME LINE 1 | | | | | | |
|---|-----------------------------------|-----------|---|--|--|--|--|
| | QUAN | MARK/PART | | | | | |
| 1 | 4 | BC-04 | ī | | | | |
| 2 | 2 | BC-15D | | | | | |
| 3 | 12 | BC-01 | | | | | |

NOTE: INSTALL WINDOW(S) FIRST BEFORE INSTALLING WINDOW FRAMING (IF NEEDED)—ACC_11

NOTE: FIELD CUT PANEL FOR FIELD LOCATED SELF FRAMING/SELF FLASHING WINDOWS.



ENDWALL FRAMING: FRAME LINE 4



NOTE:

MINOR FIELD WORK OF STRUCTURAL, SECONDARY AND PANEL/TRIM ITEMS MAY BE NECESSARY TO ENSURE PROPER FIT. SUCH WORK IS CONSIDERED A NORMAL PART OF METAL BUILDING ERECTION. A.S.C. WILL NOT HONOR BACKCHARGES FOR MINOR FIELD WORK.

ENDWALL SHEETING & TRIM: FRAME LINE 4

PANELS: 26 Ga. R-Loc - Desert 40 yr

| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. | Г |
|-------|---------------------|----------|------|------|------|-----|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | l |
| Ε | ERECTION | 06.14.17 | DK | DK | SS | |
| | | | | | | |
| | | | | | | 588 |
| | | | | | | |
| 111 | | | | | | |

| | M TABLE AME LINE | 4 | | | | | | | | |
|------------|---------------------|---------|------------------|------------|--|--|--|--|--|--|
| ◇ID | QUAN | PART | LENGTH | DETAIL | | | | | | |
| 1 | 2 | BA204 | 20'-4" | TRIM_1 | | | | | | |
| 2 3 | 2 | Q764102 | 10'-2" | TRIM_66 | | | | | | |
| | 2 | Q764122 | 12'-2" | TRIM_66 | | | | | | |
| 4 5 | 1 1 | Q765L | 6" 9 1/8" | TRIM_60 | | | | | | |
| 5 | 1 1 | AR963L | 9 1/8" | TRIM_60 | | | | | | |
| 6 | 2 | AR962 | 8 1/16" | TRIM_60 | | | | | | |
| 7 | 1 1 | Q767 | 1'-4" | TRIM_100 | | | | | | |
| 8 | 1 | Q765R | 6" | TRIM_60 | | | | | | |
| 9 | 1 | AR963R | 9 1/8" | TRIM_60 | | | | | | |
| 10 | 1 | HE073 | 7'-3" | TRIM_51 | | | | | | |
| 11 | 2 2 | Q370142 | 14'-2" | TRIM_50 | | | | | | |
| 12 | 2 | JA122 | 12'-2" | TRIM_50 | | | | | | |
| 13 | 1 | Q370122 | 12'-2" 12'-3" | TRIM_51 | | | | | | |
| 14 | _1 | HE123 | 12'-3" | TRIM_51 | | | | | | |
| | BOLT | TARIF | | ROLT TABLE | | | | | | |

| BOLT TABLE FRAME LINE 4 | | | | |
|----------------------------|------|------|------|--------|
| LOCATION | QUAN | TYPE | DIA | LENGTH |
| Columns/Raf | 2 | A325 | 1/2" | 1 1/4" |


| MEMBER FRAME | TABLE LINE 4 | | |
|-----------------|-----------------|---------|------------|
| QUAN | MARK | PART | LENGTH |
| 2 | EC-2 | 8X35C12 | 15'-1 3/4" |
| 1 | DH-1 | 8X25C16 | 11'-11" ' |
| 5 | G-1 | 8X25Z16 | 11'-11" |
| 2 | G-3 | 8X25Z16 | 5'-3 1/8" |


| | CONNECTION PLATES FRAME LINE 4 | | | | |
|---|-----------------------------------|-----------|--|--|--|
| | QUAN | MARK/PART | | | |
| 1 | 2 | BC-04 | | | |
| 2 | 2 | BC-15D | | | |
| 3 | 10 | BC-01 | | | |

NOTE: INSTALL WINDOW(S) FIRST BEFORE INSTALLING WINDOW FRAMING (IF NEEDED)—ACC_11

NOTE: FIELD CUT PANEL FOR FIELD LOCATED SELF FRAMING/SELF FLASHING WINDOWS.


| | DESCRIPTION | ENDWALL FRAMING & SH | HEETING |
|---|-------------|---------------------------|-----------------|
| Almondung | CUSTOMER | CHRIS BERTOLINO AND/OR PO | OST SCRIPTS LLC |
| \ | END USER | CHRIS BERTOLINO | |
| Greenwood Plaza Blvd, Ste#300 | SCALE | NOT TO SCALE | |
| wood Village, Colorado 80111 PHONE: 800-345-4610 www.armstrongsteel.com | 5510 | 1 SS 0WG HO.: 11 OF 16 | 04/25/17 |





| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. | |
|-------|---------------------|----------|------|------|------|----|
| P | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | l |
| Ε | ERECTION | 06.14.17 | DK | DK | SS | |
| | | | | | | |
| | | | | | | 58 |
| | | | | | | |
| | | | | | | |


| ARIASTRONO | DESCRIPTION | DETAIL DRAWINGS | |
|--|-------------|------------------------|------------------|
| AGIASTGIONO | CUSTOMER | CHRIS BERTOLINO AND/OR | POST SCRIPTS LLC |
| (+) | END USER | CHRIS BERTOLINO | |
| 9 S. Greenwood Plaza Blvd, Ste#300 | SCALE | NOT TO SCALE | |
| Greenwood Village, Colorado 80111 PHONE: 800-345-4810 www.armstrongsteel.com | 5510 | 1 DWG. NO.: 13 OF 16 | DATE: 04/25/17 |



| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. |
|-------|---------------------|----------|------|------|------|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS |
| E | ERECTION | 06.14.17 | DK | DK | SS |
| | | | | | |
| | | _ | | | |
| | | | | | |

| | DESCRIPT |
|----------------------------------|-----------------|
| AHASTRUKU | CUSTOMER |
| + | END USER |
| S. Greenwood Plaza Blvd, Ste#300 | SCALE |
| PHONE: 800—345—4610 | лов жо.: 551 |


| | DESCRIPTION | DETAIL DRAWINGS |
|-----|-------------|--|
| | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LI |
| | END USER | CHRIS BERTOLINO |
| 500 | SCALE | NOT TO SCALE |
| | 5510 | DNG. BY: SS 04/25/1 |



| ISSUE | DESCRIPTION | DATE | DRN. | CHK. | DES. | 1 |
|-------|---------------------|----------|------|------|------|----|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | 1 |
| E | ERECTION | 06,14,17 | DK | DK | SS |] |
| | | | | | | 1 |
| | | | | | | 56 |
| | | | | | | l |



| Ī | DESCRIPTION | DETAIL DRAWINGS |
|----|-------------|---|
| | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LLC |
| | END USER | CHRIS BERTOLINO |
| 00 | SCALE | NOT TO SCALE |
| | 5510 | 1 PAG 815 SS DATE: 04/25/17 |



| | | | A | CCESSORIES SCHEDULE | |
|---|------|------|-----------------|--|--------|
| # | | QUAN | SIZE | PART DESCRIPTION | PAGE # |
| 1 | WN-1 | 2 | 3'-0" X 3'-0" | 3030 HORIZ. SLIDER PBR PANEL | ** |
| 2 | WN-2 | 1 | 6'-0" X 3'-0" | 6030 HORIZ. SLIDER PBR PANEL | ** |
| 3 | DR-1 | 2 | 3'-0" X 7'-0" | 3070 WALKDOOR TYPE M WHITE | ** |
| 4 | DR-1 | 2 | 3'-0" X 7'-0" | 3070 8" DOOR FRAME KIT | ** |
| 5 | OH-1 | 1 | 12'-0" X 12'-0" | Insult OHD | ** |
| 6 | | 2 | 9" X 10'-0" | CONTINUOUS RIDGE VENT FLAT SKIRT GALV. W/ DAMPER | ** |
| 7 | LV-1 | 1 | 3'-0" X 3'-0" | FIXED LOUVER 3FT. X 3FT. WHITE | ** |
| 8 | WN-3 | 3 | 7'-0" X 1'-0" | 7010 HORIZ. SLIDER PBR PANEL | ** |
| _ | | | | | |
| _ | - | | | | |
| _ | | | | | |
| - | - | | | | - |
| - | | | | Was a second sec | |
| | | | | | |
| | | | | | |

Sag Strap (BANDSW) 2" x 24 ga. (Bottom of Purlina ONLY)

TYPICAL SAG STRAP AT GABLED ROOF

SCREW_15

(2) Philips Pancake Head (TYP)

Mote: Maximum puriln spacing is at 5'-0 Q.C.

| ISSUE | | | | CHK. | DES. | |
|-------|---------------------|----------|-----|------|------|-----|
| Р | PERMIT/CONSTRUCTION | 06.08.17 | CAF | RS | SS | |
| Ε | ERECTION | 06,14,17 | DK | DK | SS | |
| | | - | | | | 588 |
| | | | | | | |

| | | DESCR |
|---|---|--------------|
| | ARMSTROUG | CUSTO |
| | + | END U |
| | 5889 S. Greenwood Plaza Blvd, Ste#300 | SCALE |
| 1 | Greenwood VWage, Colorado 80111 PHONE: 800-345-4810 | же на: 5. |

| | DESCRIPTION | DETAIL DRAWINGS |
|---|-------------|---|
| | CUSTOMER | CHRIS BERTOLINO AND/OR POST SCRIPTS LLC |
| | END USER | CHRIS BERTOLINO |
| 0 | SCALE | NOT TO SCALE |
| | 5510 | 1 ONG BY: SS OA/25/17 ONG NO.: 16 OF 16 SSUE: E |